Sl No	Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
18	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 (Pg:182, It.No-24.15 PWD SR:2018-19)								
	For Asphalt road	Sqm							
	Sri Vinayaka temple road		2.5	272.00	0.10		68.00		
	6th A Cross		2.5	128.00	0.10		32.00		
	1st B Cross		2.5	182.00	0.10		45.50		
	3rd B Cross		2.5	178.00	0.10		44.50		
	Havnoor Layout main road		2.5	142.00	0.10		35.50		
	3rd Main road		2.5	273.00	0.10		68.25		
	1st Cross		2.5	105.00	0.10		26.25		
	Cross roads		2.5	200.00	0.10		50.00		
	Cross roads		2.5	231.00	0.10		57.75		
							427.75	454.74	194515.0
	TOTAL								**21874083.82**
	GST 12%								**2624890.06**
	PMC 1%								**250000.00**
	DPR 1%								**250000.00**
	Miscellaneous and unforseen Charges								**1026.12**
								Total	**25000000.00**

CERTIFICATE

1 The Work spot has been inspected and the work found to be necessary
2 The Estimate is prepared as per the PWD SR 2018-19 & the Approved Data Rate
3 The Provision made in estimate are adequate and essential
4 This area comes under BBMP limits.

Asst Engineer
Ward No: 14
BBMP

Asst Executive Engineer
Bagalagunte Sub-division
BBMP

Executive Engineer
Dasarahalli-division
BBMP

ADMINISTRATIVELY SANCTIONED FOR
(Rupees...250.00...Lakhs...(Two...
Hundred...Lakhs...Fifty...Thousand)...
Under the Head of Account...R-2015...
...T.P.S.....
.....
Registered as no EE(D.D.)/AS 231/19-20...Subject to conditions contained in Enclosed Memo
No:EE/DD/AS.../231/19-20...Dt:05/03/20

Exe. Eng
(DASARAHALLI) BBMP
...AE.

ನಂ.CE/dz/TS/179/18-19 ನಾಂಕ : 22/02/19
ರೂ. 250.00 lakhs
(Two fifty lakhs only)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.

ತಾಂತ್ರಿಕ ಸಹಾಯಕರು

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.